

November 14, 2023

**POLK COUNTY, A POLITICAL SUBDIVISION OF
THE STATE OF FLORIDA**

**ADDENDUM #3
BID# 23-654**

DRIFTWOOD DRIVE DRAINAGE IMPROVEMENTS-ARP

This addendum is issued to clarify, add to, revise and/or delete items of the Contract Documents for this work. This Addendum is a part of the Contract Documents and acknowledgment of its receipt shall be noted below and on the Bid Submittal Form.

Contained within this addendum: questions and answers received.

Michael Guerrero

Michael Guerrero
Sr. Procurement Analyst
Procurement Division

This Addendum sheet should be signed and submitted with your bid submittal.

Signature: _____

Printed Name: _____

Title: _____

Company: _____

BID 23-594
DRIFTWOOD DRIVE DRAINAGE IMPROVEMENTS-ARP
ADDENDUM #3

Question 1: Does the existing storm drainpipe, staying in place, need to be cleaned and videoed? If so, can a size and quantity be provided?

Answer: The contractor should clean and desilt all the existing pipes that will not be replaced within the limits of the project. The pipe size and length can be obtained from the construction plans.

Question 2: Are signed and sealed MOT plans required, or can FDOT indexes be used?

Answer: The project is anticipated to be constructed under lane closures mostly along a local road. Therefore, FDOT index can be used.

Question 3: Is a project sign required?

Answer: No project signs are required.

Question 4: Is a post video required?

Answer: No, it will not be required. For more information, please see section 430-4.8 of the FDOT specs listed on the plans.

Question 5: Do the short runs of RCP being added to the existing pipe need to be videoed?

Answer: Please see response for question #4.

Question 6: Does SD-1, SD-2 and SD-3 get a MES or does the pipe end with a plain end?

Answer: SD-1, SD-2 and SD-3 do not have MES, just a plain end.

Question 7: S-100, does the pipe just end with a plain end or tie into a structure?

Answer: S-100 has no MES or headwall, just plain end.

Question 8: Does the West end of SD-07 tie into the existing headwall?

Answer: Yes.

Question 9: Are there any yards with irrigation? If so, will irrigation replacement be paid for under the contingency item?

Answer: Yard irrigation systems were not collected on the survey. If encountered and replacement is necessary, compensation will be issued on a case-by-case basis under the contingency item.

Question 10: Will excavation and embankment be paid per truck ticket or plan quantity?

Answer: These quantities will be paid per plan quantity. For substantial error on the plan quantity, please refer to section 9-3.2 of the FDOT specs.

Question 11: When does the County expect to have the contract awarded?

Answer: Typically, the recommendation of award is made 3-4 weeks after bid opening.

Question 12: Who will make the final acceptance decisions on this project the County or FDOT?

Answer: The County will make the final acceptance decisions on this project.

Question 13: Can the contractor use a Polk County approved 3000 psi concrete mix?

Answer: Yes, the 3000-psi concrete mix is acceptable.

Question 14: Is this project unit measured or plan quantity project?

Answer: This is a plan quantity project. For substantial error on the plan quantity, please refer to section 9-3.2 of the FDOT specs.