

March 19, 2025

POLK COUNTY, A POLITICAL SUBDIVISION OF THE STATE OF FLORIDA

ADDENDUM #3 BID# 25-288

CITY OF LAKE WALES ORANGE AND CRYSTAL AVENUE PROJECT

This addendum is issued to clarify, add to, revise and/or delete items of the Contract Documents for this work. This Addendum is a part of the Contract Documents and acknowledgment of its receipt shall be noted below and on the Bid Submittal Form.

Contained within this addendum:

1. Questions received and answered.

Ken Brush

Ken Brush
Procurement Contracts Manager
Procurement Division

**This Addendum sheet should be signed and submitted with your
bid submittal.**

Signature: _____

Printed Name: _____

Title: _____

Company: _____

BID 25-288
CITY OF LAKE WALES ORANGE AND CRYSTAL AVENUE PROJECT
ADDENDUM #3

Question 1: Per bid sheet the asphalt overlay request fc 9.5 but the plans show asphalt sp 12.5:

Answer: All references on the Typical Section, Tabulation of Quantities, and Bid Sheet should be for Asphalt Concrete Friction Course, Traffic C, FC-9.5, PG 76-22 (FDOT Pay Item 337 7 82).

Question 2: Will the info for the 4 unspecified trees be forthcoming?

Answer: All tree types are identified in the Tabulation of Quantities, Sheets C-04 and C-05, and the Bid Sheet.

Question 3: Will there be any maintenance or watering required after installation?

Answer: Contractor will be responsible for watering the trees until the project is accepted by the City of Lake Wales.

Question 4: Any irrigation to be installed?

Answer: Irrigation will be installed by the City of Lake Wales.

Question 5: Landscape & Irrigation - Can you please share with us the spec on the soil for the rain garden.

Answer: Soil specifications are provided below and are to be considered as incidental to the Rain Garden cost. The bioretention soil mix is to be 60% to 70% silica sand by volume (fine to medium), with 30% to 40% organic compost such as sphagnum moss partially decomposed, 100% passing ½" sieve with a pH 3.4 to 4.8.